

Test Report

Test Name 实验名称		Geocell Performance Test 土工格室综合性能测试			
Sample Name 样品名称		Geocell 土工格室		Production Equipment 生产设备	Geocell machine line 格室机组
Specification 规 格		50-712		Production Workshop Workshop	Geocell Workshop 格室车间
Sample Head 采样负责		Chen Jing 陈 静		Production Team Team	Team A
Testing Standard 实验技术依据		GB/T 19274-2003		Testing Equipment 测试设备	Electronic universal testing machine
Testing Items And Results 实 验 项 目 和 结 果	Items 项 目			Test Result 实验结果	Evaluation 评 定
	Color 外观颜色			Black	Qualified 合格
	Height ,mm 高度, mm			50	Qualified 合格
	Welding Distance,mm 焊炬, mm			712	Qualified 合格
	Tensile strength of welded joint, N/cm 焊接处抗拉伸强度, N/cm			≥100	Qualified 合格
	Tensile yield strength of geocell Plate ,Mpa 格室片的拉伸屈服强度,Mpa			≥180	Qualified 合格
	Tensile strength of the joint between geocell, N/cm 格室组间连接处抗拉强度, N/cm		Edge of geocell plate 格室片边缘	≥100	Qualified 合格
			Middle of geocell plate 格室片中间	≥90	Qualified 合格
Test conditions 实验条件		Temperature: 20°C; Humidity: 50% 温度: 20°C ; 湿度: 50%			
Remarks 备注		Smooth, uniform, no defects, this test report is only responsible for the sample 产品外观均匀, 无损伤, 此检测报告仅对样品负责			

Reviewer: Wng Xiaoli

Main Tester: L. Cheng

December 16, 2025

